

DESCRIPTION

This work shall consist of relocating existing loose laid stone wall in close conformance with the lines and grades as shown on the plans and as directed by the ENGINEER.

MATERIAL

No. 2 crushed stone shall meet the requirements as outlined in NYSDOT Standard Specifications, Material Designation 703-0201 (Crushed Stone), latest revision.

CONSTRUCTION DETAILS

Caution shall be taken in removing the existing stone so as to avoid breakage. Foreign or extraneous matter shall be removed from the stone. This operation must be performed such that the integrity of the stone is maintained. The work shall be phased so as to disassemble the existing stone wall and reassemble in the new location as one operation.

The stone wall shall be constructed to match the existing pattern, size and shape exactly.

A 6-inch crushed stone course shall be placed on the approved subgrade, and shall extend 6 inches beyond the area of stone wall. This 6-inch crushed stone foundation shall be evenly graded, compacted by six passes with a mechanical tamper over the entire area to provide a uniformly even surface.

The stone wall shall be constructed on the crushed stone foundation.

After the stone wall has been removed, the subbase material shall be removed and properly disposed of.

METHOD OF MEASUREMENT

The quantity to be measured for payment shall be the number of linear feet of stone wall relocated.

BASIS OF PAYMENT

The unit price bid per linear foot of stone wall relocated shall include the cost of: Disassembling and reassembling existing stone wall; cleaning; placement of crushed stone bedding; excavation; and furnishing all labor material and equipment necessary to complete the work.

Payment will be made under:

<u>Item No</u>	<u>Item</u>	<u>Pay Unit</u>
C202.04	Relocate Stone Wall	LF