



Purchasing and Central Services

Monroe County, New York

Maggie Brooks
County Executive

Dawn C. Staub
Purchasing Manager

ADDENDUM NO: 2

BID PROJECT NO: 1204-10 INDUSTRIAL FLOOR RESURFACING - MC
JAIL RECEPTION HOUSING

DATE: January 5, 2011

BIDDERS PLEASE NOTE:

ATTACHED ARE TWO (2) PAGES TO BE REPLACED/ADDED TO YOUR BID SPECIFICATION PACKAGE.

REPLACE PAGE 8. Note Paragraph 4.03, B., 1. has been added.

ADD PAGE 25. Diagram of Jail Reception Housing Men's and Women's Holding Cells and Commons Area.

SIGN this Addendum below acknowledging receipt and understanding and either INSERT in document or RETURN under separate cover.

MONROE COUNTY

Sharon A. Berndt

Sharon A. Berndt, Buyer
(585) 753-1110

The undersigned bidder acknowledges receipt and understanding of **Addendum No. 2 to Bid Project No. 1204-10 INDUSTRIAL FLOOR RESURFACING - MC JAIL RECEPTION HOUSING.**

_____, 2011
Date

Name of Company

Authorized Signature

Title

4.00 RESURFACING & RESTORATION

Men's & Women's Holding Cells & Commons Area:

This area is 7,415 sq. ft. w/ 326 lf. of cove done in 4 phases in a Caramel color. The cove is only in the common areas, not in the jail holding cells.

4.01 TIME TABLE

- A. The project areas will be done in three section phases and each work area will be completed one section at a time.
- B. The hours of operation will be 7:30 A.M. - 6:00 P.M. Each section will take no longer than 7 working days.
- C. If there is a spike in the inmate population of the downtown jail, work will need to be suspended and the process will continue as soon as practicable.

4.02 WORK AREA

- A. Floors must be free of standing water, oil free.
- B. Floors must remain free from traffic for a minimum of 24 hours after installation.

4.03 OWNER RESPONSIBILITY

- A. Owner will be responsible for glass and equipment protection, dumpster, effective lighting and power.
- B. Owner is responsible to removal of all furnishings, equipment, existing cove base, VCT tiles and excess mastic glue.
 - 1. Before proceeding with the floor resurfacing project, the successful bidder will need to supply a statement to Owner stating that the existing cove base, VCT tiles and excess mastic glue have been removed by the Owner, and further state that the floor is suitably prepared for the installation of the industrial flooring or make recommendations as to what still needs to be accomplished by the Owner from paragraph 4.03, B.

MEN'S AND WOMEN'S HOLDING CELLS AND COMMONS AREA

