ITEM 686.9917 REMOVAL OF COAXIAL CABLE

DESCRIPTION

Under this item the CONTRACTOR shall remove existing coaxial cable as indicated on the plans.

CONSTRUCTION REQUIREMENTS

Prior to removing the cable, the connectors shall be removed and returned to the MCDOT Division of Traffic Engineering.

METHOD OF MEASUREMENT

The quantity to be paid for shall be the number of linear feet of cable removed.

BASIS OF PAYMENT

The price bid shall be a unit price per linear feet for removing all cable including all labor, tools and equipment required for removal.

Payment shall be made after testing and delivery to the MCDOT Division of Traffic Engineering.

Payment will be made under:

Item No.	<u>Item</u>	Pay Unit
686.9917	Removal of Coaxial Cable	LF

686-9917.doc 1 of 1 Last Revised 1-05