

ITEM 502.81M INSTALL JOINT CAULK

DESCRIPTION

Under this item the CONTRACTOR shall install joint caulk along the bottom of the exposed edge of the newly reconstructed abutment backwall. Joint caulk shall also be installed around the perimeter, between the framing and new grating, of the newly installed fiberglass scuppers.

MATERIALS

The caulking compound shall conform to all the provisions of NYSDOT Standard Specifications, Subsection 705-06 Caulking Compound for Structures, latest revision.

CONSTRUCTION DETAILS

Caulking compound shall be placed where shown on the Plans or where directed by the ENGINEER.

METHOD OF MEASUREMENT

The quantity to be paid for under this item will be the number of linear meters of caulking compound installed in accordance with the Plans and as directed by the ENGINEER.

BASIS OF PAYMENT

The unit price bid per linear meter shall include the cost of all labor, materials, and equipment necessary to complete the work.

Payment will be made under:

<u>Item No</u>	<u>Item</u>	<u>Pay Unit</u>
502.81M	Install Joint Caulk	M