

DESCRIPTION

Work covered under this specification shall include digging up the tagged trees, balling and burlapping, heeling-in and maintenance during storage.

MATERIAL

Refer to the Special Note "Supplemental Landscape Development Specifications".

CONSTRUCTION DETAILS

- A. Remove trees with earth ball intact around root system. Soil ball size shall comply with the recommendations and requirements of ANSI 260.1 'American Standard for Nursery Stock'. Ball and burlap trees and store on site as directed by the ENGINEER. Do not bend or bind-tie trees in such a manner as to damage bark, break branches, or destroy natural shape. Provide protective covering during transport. Do not drop balled and burlapped transplants during transport and storage.
- B. Heel-in balled and burlapped transplants until time of replanting. Plants shall be heeled-in at the storage site on same day of digging. No trees shall be dug up and exposed longer than a normal work day.
- C. Water and mulch plants as necessary to maintain optimum health of plant until replanting occurs.
- D. Deliver plants after preparations for planting have been completed and plant immediately. If planting is delayed more than six hours after delivery, set plants in shade, protect from weather and mechanical damage and keep roots moist by covering with mulch, burlap or other acceptable means of retaining moisture.

METHOD OF MEASUREMENT

The quantity measured for payment shall be the number of trees dug up and re-installed, measured in place by the ENGINEER.

BASIS OF PAYMENT

The unit price bid shall include the cost of digging up the installed trees, balling and burlapping, heeling-in and maintenance during storage and re-planting as per the Supplemental Landscape Development Specifications.

Payment will be made under:

<u>Item No.</u>	<u>Item</u>	<u>Pay Unit</u>
611.99 M	Tree Transplanting	EA