

**ITEM 686.9917M      REMOVAL OF COAXIAL CABLE**

**DESCRIPTION**

Under this item the CONTRACTOR shall remove existing coaxial cable as indicated on the plans.

**CONSTRUCTION REQUIREMENTS**

Prior to removing the cable, the connectors shall be removed and returned to the MCDOT Division of Traffic Engineering.

**METHOD OF MEASUREMENT**

The quantity to be paid for shall be the number of linear meters of cable removed.

**BASIS OF PAYMENT**

The price bid shall be a unit price per linear meter for removing all cable including all labor, tools and equipment required for removal.

Payment shall be made after testing and delivery to the MCDOT Division of Traffic Engineering.

Payment will be made under:

<b><u>Item No.</u></b>	<b><u>Item</u></b>	<b><u>Pay Unit</u></b>
686.9917M	Removal of Coaxial Cable	M