

GENERAL NOTES:

THE ELEMENTS OF THIS PAGE KNOWN AS " SOIL EROSION AND SEDIMENT CONTROL" SHALL BE USED DURING CONSTRUCTION IN ANY AREA WHERE FINE MATERIALS MAY ENTER THE WATERS OF THE STATE OF NEW YORK. EXACT LIMITS OF ENVIRONMENTAL TREATMENT SUBJECT TO WATER ELEVATION AT THE TIME OF CONSTRUCTION.

NOTES:

1. THE CONTRACTOR SHALL COMPLY WITH ALL PROVISIONS OF THE N.Y.S. DEPARTMENT OF ENVIRONMENTAL CONSERVATION WATER QUALITY CERTIFICATION AND/OR FRESH WATER WETLANDS PERMIT AND/OR CORPS OF ENGINEERS' PERMIT (IF APPLICABLE).
2. ALL STREAM CHANNEL WORK SHALL BE LIMITED TO WITHIN THE DESIGNATED RIGHT-OF-WAY, EASEMENT, OR T.O. LIMITS, OR RELEASE.
3. HAY BALE DIKES MAY BE SUBSTITUTED FOR SILT FENCE AS APPROVED BY THE ENGINEER.
4. PERIODIC CLEANING AND INSPECTION OF THE TEMPORARY SOIL EROSION AND SEDIMENT CONTROL DEVICES SHALL BE NECESSARY, A.Q.B.E. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES MAY BE REQUIRED DUE TO VARIATION IN SITE CONDITIONS, A.Q.B.E.. COST TO BE INCLUDED IN ITEM 209.01 M.
5. STRAW BALE AND/OR SILT FENCES INSTALLED ALONG WORK LIMITS FOR THE PURPOSE OF SLOWING OVERLAND (SHEET) FLOW SHALL BE ARRANGED PERPENDICULAR TO THE DIRECTION OF THE SHEET FLOW. SUCH INSTALLATION MAY REQUIRE SHORT, STAGGERED SEGMENTS OF FENCE IN ORDER TO BE LOCATED WHOLLY WITHIN THE DESIGNATED WORK LIMITS.