

ITEM 608.18M RESET WOOD WALK

DESCRIPTION

The work shall consist of removing existing wood sidewalk storing and resetting wood walk in close conformance with the lines and grades as shown on the plans and as directed by the ENGINEER.

MATERIALS

Materials shall meet the requirements specified in the following subsections of NYSDOT Section 700:

Crushed Stone	703-0201
Mortar Sand	703-03
Water	712-01

CONSTRUCTION DETAILS

Caution shall be taken in removing the existing wood sidewalk so as to avoid breakage. Foreign or extraneous matter shall be removed from the wood. This operation must be performed such that the integrity of the wood is maintained. The wood should be placed on level ground which will provide even bearing and allow free movement of air through and around the wood. The work shall be phased so to minimize the duration of storage for the wood sidewalk.

After the wood sidewalk has been removed, the bed and subbase material shall be removed and properly disposed of.

Wood boards shall be placed in the pattern to match the existing and provide a uniformly even surface. Joints shall be hand tight to match existing joints. No wood boards shall be laid in freezing weather.

A 150mm crushed stone course shall be placed on the approved subgrade, and shall extend 150mm beyond the area of wood walk. A 50mm layer of sand shall be placed over the crushed stone subbase. The sand shall be evenly graded, compacted by means of two passes over the entire area with a mechanical tamper to provide a uniformly even surface.

Wood boards shall be placed on the sand bed, and constructed to match the existing wood sidewalk construction.

Dry fine sand shall be swept over the wood boards until the joints are completely filled and the joints lightly fogged with water. Wood walk shall be cleaned of excess sand.

METHOD OF MEASUREMENT

The quantity to be measured for payment shall be the number of square meters of wood sidewalk reset.

ITEM 608.18M RESET WOOD WALK

BASIS OF PAYMENT

The unit price bid per square meter of wood sidewalk reset shall include the cost of removing and reinstalling existing wood materials; saw cutting; water; cleaning; sand foundation; crushed stone; excavation; and furnishing all labor material and equipment necessary to complete the work.

Payment will be made under:

<u>Item No.</u>	<u>Item</u>	<u>Pay Unit</u>
608.18M	Reset Wood Walk	SM