

**DESCRIPTION**

This work consists of furnishing and sowing grass seed, fertilizer, mulch and mulch anchorage on areas within the contract limits.

**MATERIAL**

Seeds shall be as specified in sub-section 713-04, and further specified as follows:

<b><u>Name</u></b>	<b><u>Variety</u></b>	<b><u>Min. % Germination</u></b>	<b><u>Grams Pure Live Seed Per Sq. Meter</u></b>
Red Fescue (Festuca Rubra)	Commercial 85	46.37%	8.3g
Kentucky Bluegrass (Poa Pratensis)	Commercial 75	39.66%	7.1g
Perennial Ryegrass (Lolium Perene)	Commercial 90	13.97%	2.5g
Total Grams pure live seed per square meter			17.9

Fertilizer shall be as specified for 713-03 Fertilizer, Type No. 3 (10-6-4).

Mulch shall be as specified for 713-19 Straw. Anchorage shall be "Silvafiber" or approved equal.

Construction details shall comply with sub-section 610-3 except as herein modified. The rate of fertilizer application shall be 9.0 grams of nitrogen per square meter and the rate of seed application shall be 17.9 grams of pure live seed per square meter. Method No. 2 shall apply. The rate of mulch application shall be 672.5g/SM. The rate of mulch anchorage application shall be 44.8g/SM.

Seeding shall be measured in square meters of surface area computed to the nearest unit thereof which have been acceptably seeded. Seeding shall be paid for at the unit price bid per square meter, which payment shall constitute full compensation for furnishing all labor, materials, equipment and incidentals to complete the work as specified.

**BASIS OF PAYMENT**

Payment will be made under:

<b><u>Item No.</u></b>	<b><u>Item</u></b>	<b><u>Pay Unit</u></b>
610.0202M	Seeding	SM

