

DESCRIPTION

This work shall include the removal of existing signs designated on the plans or as specified by the ENGINEER. The sign components shall include sign panels, upright supports, bracing and structures. Signs designated for removal shall be delivered to the Monroe County Department of Transportation, Sign Fabrication Shop, 350 East Henrietta Road, at no extra cost to the COUNTY.

REMOVAL OF SIGNS

Existing traffic signs requiring removal only, shall be removed from the work site in a neat and workmanlike manner to the satisfaction of the ENGINEER.

REMOVAL OF CONCRETE SIGN FOOTINGS

All concrete sign footings shall be cut to a depth of 150 mm below existing ground and be replaced with suitable material as specified by the ENGINEER.

METHOD OF MEASUREMENT

The quantity to be paid for will be the number of completely removed signs having sign areas of the following sizes:

SIZE A:	0 to 0.9 Square Meters
SIZE B:	1.0 to 1.9 Square Meters
SIZE C:	2.0 to 3.7 Square Meters
SIZE D:	3.8 to 9.3 Square Meters
SIZE E:	Over 9.3 Square Meters

BASIS OF PAYMENT

The unit price bid for removing an existing installation shall be compensation in full for the furnishing of all labor, equipment and materials necessary to complete the work to the satisfaction of the ENGINEER.

Payment will be made under:

<u>Item No.</u>	<u>Item</u>	<u>Pay Unit</u>
686.41M	Removal of Signs - Size A (0.0-1.0 SM)	EA
686.42M	Removal of Signs - Size B (1.0-1.9 SM)	EA
686.43M	Removal of Signs - Size C (2.0-3.7 SM)	EA
686.44M	Removal of Signs - Size D (3.8-9.3 SM)	EA
686.45M	Removal of Signs - Size E (over 9.3 SM)	EA