

DESCRIPTION

Under this item the CONTRACTOR shall remove existing anchor bolt type pole bases and controller bases that are no longer required, and restore the area disturbed by the base removal.

MATERIALS

All materials used for restoration shall conform to the appropriate section of the NYSDOT Standard Construction and Material Specifications and as ordered by the ENGINEER.

CONSTRUCTION DETAILS

The CONTRACTOR shall remove the entire concrete base, or remove the top 550 mm to 600 mm of the concrete and anchor bolts. The CONTRACTOR shall backfill and restore the entire area disturbed by the base removal to an elevation level with existing ground. The restored surface area shall be replaced with material that matches existing adjacent surfaces. Sub-base course backfill material shall be consistent with the type of material used to restore the surface area.

METHOD OF MEASUREMENT

This item will be measured for payment as the number of each concrete base removed in accordance with the contract documents and as directed by the ENGINEER.

BASIS OF PAYMENT

The unit price bid for this item shall include the furnishing of all labor, materials, tools, equipment, and incidentals as necessary to complete the work, including excavation, removal and disposal of bases, and all materials for backfill, and to match adjacent surface area.

Payment will be made under:

<u>Item No.</u>	<u>Item</u>	<u>Pay Unit</u>
686.5099M	Concrete Base Removal (Pole and Controller)	EA