



NOTES:

1. BACKFILL WILL BE MADE WITH ITEM 203.07 TO THE BOTTOM OF TEMPORARY PAVEMENT, OR TO THE BOTTOM OF SUBBASE.
2. SLOPE SHEETING & BRACING PER OSHA, SPECIFICATION. TRENCH SHIELD OR SHEETING TO BE LIFTED ABOVE THE SPRING LINE. FOR EXCAVATIONS GREATER THAN 5', THE CONTRACTOR SHALL USE ONE OF THE FOLLOWING TREATMENT OPTIONS:
  - A. LAYBACK OF TRENCH AT 1:1.5 (H:V). NO ADDITIONAL PAYMENT WILL BE MADE FOR EXCAVATION OF BACKFILL BEYOND THE TRENCH WIDTH OF O.D. + 2'.
  - B. USE ITEM 552.17 - SHIELDS AND SHORING.
3. WHERE STORM SEWER CROSSES PREVIOUSLY INSTALLED SANITARY SEWER, WATER OR GAS MAIN, ETC. TRENCH SHALL BE EXCAVATED DOWN TO THE PREVIOUSLY LAID UTILITY AND BACKFILL WITH #2 CRUSHED STONE COMPACTED IN 6" LIFTS TO INSURE ADEQUATE SUPPORT.
4. 6" STONE BEDDING, CONSISTING OF A BLENDING OF #1 AND #2 STONE, IS REQUIRED FOR SANITARY AND STORM SEWER INSTALLATIONS WITH CRUSHED STONE HAUNCHING TO A MINIMUM OF ONE-HALF OF THE PIPE DIAMETER ON THE SIDE OF THE PIPE. PAYMENT TO BE INCLUDED UNDER ITEM 203.07 SELECT GRANULAR FILL.

STORM SEWER TRENCH IN PAVED AREA

NOT TO SCALE

REVISED 3/15/21